

FLORIDA

DR 11 & 16 PHASE 2 BMP

**LOCATION:**

Fort Meade, FL

COMPLETION:

June 2021

Construction of 6,200 LF of BMP system (earthen berms and stormwater control ditches) along the perimeter of a new mining area. The purpose of the berm system is to prevent stormwater from leaving the mining area. Work consisted of 70,000-cyds of earthwork, installation of culverts and drains, erosion protection, and sodding.